



Economic Development, Investment, Trade & Natural Resources

Petroleum Branch

360-1395 Ellice Ave, Winnipeg, MB R3G

3P2

T 204-945-6577 F 204-945-0586

www.manitoba.ca

WEEKLY WELL ACTIVITY REPORT

PETROLEUM INDUSTRY ACTIVITY REPORT

(January 5/26 -- March 02/26)

<u>DRILLING ACTIVITY</u>	To Mar 02/26	To Mar 03/25	2025 Total
Drilling Licences Issued	19	22	187
Licences Cancelled	2	2	9
Vertical Wells Drilled	1	0	0
Horizontal Wells Drilled	37	43	173
Stratigraphic Test Holes Drilled	0	0	0
Wells Drilled - Total	38	43	173
No. of Metres Drilled	83089	99741	427703
Wells Re-entered	0	1	1
Wells Being Drilled	3	2	0
No. of Active Rigs	3	4	0
Wells Licenced but Not Spudded	48	31	72
Wells Completed as Potential Oil Wells	37	43	166
Wells Abandoned Dry	0	0	0
Wells Drilled but Not Completed	0	0	0
Other Completions	1	0	7
New Wells on Production	34	32	0
<u>GEOPHYSICAL ACTIVITY</u>			
Geophysical Programs Licenced	0	0	2
Licences Cancelled	0	0	0
Kilometers Licenced	0.00	0.00	50.31
Kilometers Run	0.00	0.00	50.31
	2026	2025	
<u>OIL PRICES</u>			
<u>(Average)</u>	\$/M3 \$/BBL	\$/M3 \$/BBL	
Month of January	\$472.91 \$75.15	\$580.77 \$92.28	
Month of February	\$0.00 \$0.00	\$571.47 \$90.81	
<u>OIL PRODUCTION (M3)</u>	2026	2025	
Month of February	177,934.4 M3	180,066.2 M3	

WEEKLY WELL ACTIVITY REPORT

02 March 2026

Lic. No.: 12418	<p>Tundra Manson HZNTL 5-4-13-28 (WPM) UWI: 100.05-04-013-28W1.00 - Leg #1 Spud Date: 26-Feb-2026 K.B. Elevation: 502.48 m Surface Casing: 244.50 mm @ 145.00 m with 7.5 t Intermediate Casing: 177.80 mm @ 814.00 m with 17.1 t Status: Drilling Ahead (DR) Drilling Ahead: 02-Mar-2026</p>
Lic. No.: 12460	<p>Tundra Daly Sinclair HZNTL A8-21-10-28 (WPM) UWI: 102.08-21-010-28W1.00 - Leg # Spud Date: 28-Feb-2026 K.B. Elevation: 516.22 m Surface Casing: 244.50 mm @ 143.00 m with 7.5 t Status: Drilling Ahead (DR) Drilling Ahead: 02-Mar-2026</p>
Lic. No.: 12468	<p>East Manson Unit No. 2 HZNTL B4-3-13-28 (WPM) UWI: 103.04-03-013-28W1.00 - Leg #1 Finished Drilling: 25-Feb-2026 Total Depth: 2210.00 m Rig Released: 26-Feb-2026 Surface Casing: 244.50 mm @ 137.00 m with 7.5 t Intermediate Casing: 177.80 mm @ 812.00 m with 16.5 t Status: Waiting On Service Rig (WOSR) Waiting On Service Rig: 26-Feb-2026</p>
Lic. No.: 12471	<p>Tundra Daly Sinclair HZNTL 16-15-10-28 (WPM) UWI: 100.16-15-010-28W1.00 - Leg # Spud Date: 24-Feb-2026 K.B. Elevation: 513.69 m Finished Drilling: 27-Feb-2026 Total Depth: 2266.00 m Rig Released: 27-Feb-2026 Surface Casing: 219.10 mm @ 142.00 m with 9.2 t Production Casing: 139.70 mm @ 2266.00 m with 39.0 t Status: Waiting On Service Rig (WOSR) Waiting On Service Rig: 27-Feb-2026</p>
Lic. No.: 12472	<p>Tundra Virden SWD DIR 14-2-9-25 (WPM) UWI: 102.14-02-009-25W1.00 Status: Completing (COMP) Completing: 26-Feb-2026</p>

Lic. No.: 12475 Tundra Daly Sinclair Prov. HZNTL B1-1-10-28 (WPM)
 UWI: 103.01-01-010-28W1.00 - Leg #
 Finished Drilling: 23-Feb-2026
 Total Depth: 2116.00 m
 Rig Released: 24-Feb-2026
 Surface Casing: 244.50 mm @ 135.00 m with 7.0 t
 Production Casing: 139.70 mm @ 2116.00 m with 31.0 t
 Status: Waiting On Service Rig (WOSR)
 Waiting On Service Rig: 24-Feb-2026

Status: Completing (COMP)
 Completing: 26-Feb-2026

Lic. No.: 12482 Daly Unit No. 4 HZNTL 1-35-9-28 (WPM)
 UWI: 103.01-35-009-28W1.00 - Leg #
 Status: Completing (COMP)
 Completing: 22-Feb-2026

Lic. No.: 12494 Tundra Daly Sinclair SWD A1-27-9-29 (WPM)
 UWI: 105.01-27-009-29W1.00
 Finished Drilling: 27-Feb-2026
 Total Depth: 1845.00 m
 Rig Released: 28-Feb-2026
 Surface Casing: 244.50 mm @ 201.00 m with 10.0 t
 Intermediate Casing: 177.80 mm @ 1457.00 m with 28.0 t
 Status: Waiting On Service Rig (WOSR)
 Waiting On Service Rig: 28-Feb-2026

Lic. No.: 12496 Tundra Daly Sinclair HZNTL 13-12-10-29 (WPM)
 UWI: 102.13-12-010-29W1.00 - Leg #1
 Status: Completing (COMP)
 Completing: 24-Feb-2026

Lic. No.: 12502 Sinclair Unit No. 13 HZNTL A5-33-8-29 (WPM)
 UWI: 102.05-33-008-29W1.00 - Leg #
 Spud Date: 28-Feb-2026
 K.B. Elevation: 529.35 m
 Status: Drilling Ahead (DR)
 Drilling Ahead: 02-Mar-2026

Lic. No.: 12507 Sinclair Unit No. 6 Prov. HZNTL 9-34-8-29 (WPM)
 UWI:103.09-34-008-29W1.00

Sinclair Unit No. 6 Prov. HZNTL 09-34-08-29 (WPM)
 Licence Issued: 25-Feb-2026
 Licensee: Tundra Oil and Gas
 Mineral Rights: Tundra Oil and Gas
 Contractor: Ensign Drilling Inc. - Rig# 10
 Surface Location: 12B-34-8-29
 Co-ords: 647.79 m S of N of Sec 34
 60.00 m E of W of Sec 34
 Grd Elev: 524.80 m
 Proj. TD: 2346.10 m (Mississippian)
 Field: Daly Sinclair
 Classification: Non Confidential Development
 Status: Location(LOC)

Lic. No.: 12508 Tundra Daly Sinclair HZNTL C16-6-10-28 (WPM)
 UWI:104.16-06-010-28W1.00

Tundra Daly Sinclair HZNTL C16-06-10-28 (WPM)
 Licence Issued: 25-Feb-2026
 Licensee: Tundra Oil & Gas Limited
 Mineral Rights: Tundra Oil & Gas Limited
 Contractor: Ensign Drilling Inc. - Rig# 12
 Surface Location: 12C-6-10-28
 Co-ords: 478.30 m S of N of Sec 6
 60.00 m E of W of Sec 6
 Grd Elev: 520.09 m
 Proj. TD: 2175.85 m (Mississippian)
 Field: Daly Sinclair
 Classification: Non Confidential Development
 Status: Location(LOC)

WELLS RELEASED OFF CONFIDENTIAL

The following wells were released from confidential during the last week. To obtain well or production data for these wells, please contact Paulette Seymour at (204) 945-6575.

<u>Lic. No.</u>	<u>Well Name and Location</u>	<u>Field/Pool Code</u>
12435	Cromer Unit No. 3 HZNTL 3-14-9-28 (WPM)	1
12463	Tundra Daly Sinclair HZNTL B1-20-9-29 (WPM)	1
12487	Tundra Pierson HZNTL B6-15-2-28 (WPM)	7